

CERTIFIED ACOUSTICS

Publisher	<b>Imprint</b> Fural Systeme in Metall GmbH Cumberlandstraße 62 4810 Gmunden Austria July 2020 Timo Schwach [Title, page 14, 64] stauss processform gmbh [page 4, 5, 6, 7, 8, 9, 46, 47, 52, 53, 60, 61, 96, 97] Johannes Eder [page 12, 16, 74] Roland Halbe [page 18] Roland Tilleman [page 20] Roman Bönsch [page 22] Dietmar Strauss [page 24] To Kuehne [page 26, 62, 66, 68] Alfred Wolsetschläger [page 28] Cosmin Dragomir [page 30] Peter Eder [page 32, 34] Franz Rindlisbacher [page 36] Volker Lau, konturlicht [page 38] Lukas Kirchgasser [page 40] Jogi Hild [page 42] Franz Rindlisbacher [page 44] Kurt Kubal [page 48] Gerd Kressl [page 50] Peter Kubelka [page 54] Schunk [page 56] Piero Mollica [page 58] Victor S. Brigola [page 70, 80] H.G. Esch [page 68] Herbert Brunnmeier [page 72] Dirk Freytag [page 76] Lukas van der Wee (Cepezed) [page 78] Hennie Raaymakers [page 82] Achim Frank [page 98] stauss processform gmbh, Munich
State Photos	Austria July 2020 Timo Schwach [Title, page 14, 64] stauss processform gmbh [page 4, 5, 6, 7, 8, 9, 46, 47, 52, 53, 60, 61, 96, 97] Johannes Eder [page 12, 16, 74] Roland Halbe [page 18] Roland Tilleman [page 20] Roman Bönsch [page 22] Dietmar Strauss [page 24] To Kuehne [page 26, 62, 66, 68] Alfred Wolsetschläger [page 28] Cosmin Dragomir [page 30] Peter Eder [page 32, 34] Franz Rindlisbacher [page 36] Volker Lau, konturlicht [page 38] Lukas Kirchgasser [page 40] Jogi Hild [page 42] Franz Rindlisbacher [page 44] Kurt Kubal [page 48] Gerd Kressl [page 50] Peter Kubelka [page 54] Schunk [page 56] Piero Mollica [page 58] Victor S. Brigola [page 70, 80] H.G. Esch [page 68] Herbert Brunnmeier [page 72] Dirk Freytag [page 76] Lukas van der Wee (Cepezed) [page 78] Hennie Raaymakers [page 82] Achim Frank [page 98] stauss processform gmbh, Munich
Concept and design	
Illustrations	
Editor	
Paper	
Font	
Print	
	confirms the compensation of greenhouse gas emissions through additional climate protection projects. ClimatePartner-ID 11293-2007-1001

**Fural**  
Systeme in Metall GmbH  
Cumberlandstraße 62  
4810 Gmunden  
Austria  
Management:  
Christian Demmelhuber

T +43 7612 74 851 0  
F +43 7612 74 851 11  
E fural@fural.at  
W fural.com  
Sitz Gmunden  
GS Wels  
FN 23 57 11  
UID ATU 62 76 33 34

<b>Introduction</b>
4 We are acoustic ceilings
6 We think in terms of architecture
8 Why use metal for acoustic ceilings?
10 Acoustics terminology
12 Practical example

<b>Acoustic metal ceilings</b>
14 Metal ceilings 1–9
32 Effect of the air cavity
34 Effect of acoustic infills 1–2
38 Effect of the acoustic infill thickness
40 Effect of the acoustic fleece
42 Effect of heavy-duty acoustic infills 1–2

<b>Acoustic expanded metal ceilings</b>
48 Expanded metal ceilings
50 Effect of the acoustic infills

<b>Acoustic cooling and heating ceilings</b>
54 Cooling ceilings 1–2
58 Cooling ceilings 3 (Temperon)

<b>Acoustic floating ceilings</b>
62 Terms
64 Practical example
66 Floating ceilings
68 Cooling floating ceilings 1–2

<b>Acoustic walls</b>
72 Acoustic walls 1–2
76 L-absorbers

<b>Longitudinal sound insulation</b>
78 Terms
80 Clip-in strip-grid ceilings
82 Strip-grid ceilings

<b>Appendix</b>
84 Tested perforation overview 1–5
94 Untested perforation overview

# WE ARE ACOUSTIC CEILINGS

## We are family!

Since the first half of 2019, the companies **Fural Systeme in Metall GmbH** in Gmunden (Austria), **Dipling Werk GmbH** in Frankfurt/Hungen (Germany) and **Metalit AG** in Büron (Switzerland) have constituted a strong, international corporate group in the acoustic ceiling sector.

In this international partnership, we are pooling decades of experience in development and production with the understanding of the needs of the respective regional markets.

We regard ourselves as quality leaders in acoustic ceilings, and therefore as your primary contact for aesthetically, technically and logically challenging architectural and building projects.

**"Metal acoustic ceilings are efficient, contemporary, sustainable and aesthetic structural components."**  
(Dirk Freytag, CTO)

Bison Offices, Sursee  
 - Leuenberger Architects  
 - Atrium  
 - Perforation Rd 1.5 – 22 %  
 - Colour RAL9016 traffic white  
 - Hang-in system H28

## The benefits of metal ceilings as acoustic ceilings

Our systems combine outstanding acoustic properties and a high-quality appearance with functionality and durability. This combination creates a pleasant room atmosphere that impresses developers and users alike. Architects and installers hold us in high regard for our easily installed, perfected acoustic metal ceiling systems and our service-oriented project handling.


Our acoustic ceilings can also be fitted with additional functions, such as air conditioning (cooling, heating, ventilation) or lighting. Likewise, the product properties can be enhanced in terms of fire protection, hygiene (hospitals and laboratories) or resistance to ball impact (kindergartens, schools and sports halls). Ceiling components are manufactured on state-of-the-art production systems, which can produce everything from individual pieces to high volumes with maximum precision.

The metal ceilings are delivered with finished surfaces to the construction site, thereby ensuring quick and simple processing and short construction processes.

Our products are sustainable, because they consist of easily processed materials that can either be reused or straightforwardly recycled.

## Metal acoustic ceilings impress with their

- Aesthetics (e.g. expanded metal)
- Functionality
- High value
- Sustainability
- Quality
- Durability
- Hygiene
- Easy serviceability
- Combination with fire protection



# WE THINK IN TERMS OF ARCHITECTURE

We think in terms of the categories **city, building, room and user**, and not in terms of square metres of acoustic ceiling. We take you and your projects seriously and search together with you for the best solution, particularly if it first has to be developed.

We see ourselves as your system partner for **high-quality architecture components** and look forward to collaborating with you!

At the end, we can both be proud of what we have achieved and look forward to working together for many years.

"The details are not the details – they are the design."  
(Charles Eames, 1907–1978)

Bison Offices, Sursee  
- Leuenberger Architects  
- Offices  
- Perforation Rd 1.5 – 22%  
- Colour RAL 9016 traffic white  
- Floating ceiling

# WHY USE METAL FOR ACOUSTIC CEILINGS?

Metal ceilings are hard, but thanks to the materials and operations used in their production, they act as perfect broadband absorbers. The starting point is sheet steel or aluminium with a low material thickness (0.5–1.0 mm). In combination with various hole patterns/perforations, the acoustic fleece and the overlying ceiling void, very good sound absorption values are achieved.

A metal ceiling alone allows a room to be made acoustically comfortable. The processing steps result in sturdy yet lightweight designs. The modularly produced system parts arrive at the installation location with finished surfaces. This means that rooms are ready for occupation after a short construction period. Comprehensive tests provide for various acoustic and structural design options. Our products and systems are characterised by:

- Delivery with finished surfaces
- Dust-free delivery and installation
- Durability
- Cleanability/hygiene
- Resistance to ball impact
- Serviceability
- Reversibility
- Reusability
- Unmixed recycling
- Large selection of possible perforations
- Easy, precise integration of technical elements, e.g. lighting and ventilation
- Optimum combinability with heating and cooling elements
- Aesthetics (we offer numerous colours and different surfaces, e.g. our light-scattering Parzifal® hydro-stove-enamel lacquer)

**"Our hands and machines make metal soft, open and light. It becomes a material that complies with contemporary architecture and its processes."**  
**(Christian Demmelhuber, Managing Director Fural, Metalit, Diplng)**

**Office building, Töging**  
- Hinterschweifinger Projekt GmbH  
- Atrium  
- Perforation Rq 0.7 - 4%  
- Colour RAL 9016 traffic white  
- Floating ceiling

# ACOUSTICS TERMINOLOGY

## Sound and sound level

The term "sound" refers to localised vibration and the propagating waves. These can occur in air (**air-borne sound**) or in solid materials (**structure-borne sound**). If floors, ceilings and stairs are stimulated to vibrate by footfall, this is referred to as **impact sound**.

The sound intensity is designated with sound level L and specified in the decibel (dB) unit.

## Acoustic quality

The term "acoustic quality" describes the interaction of the acoustic factors of a room for such sound events as music or speech with reference to the individual location of the person listening.

Rather than any physical properties of the room, the acoustic quality describes audio-physiological and audio-psychological effects on the listeners.

Acoustic quality is therefore not a clearly ascertainable quantity. It also depends on individual and subjective factors, for example on hearing capacity and listening experience.

However, the aim of a good acoustic plan should also be to include people with poorer hearing and therefore to achieve generally good average audibility.

## Sound absorption area

The so-called **equivalent sound absorption area**, A, of a component is calculated by multiplying its area with the sound absorption coefficient,  $\alpha$ .

All boundary surfaces,  $S_i$ , of a room have individual sound absorption coefficients,  $\alpha_i$ , which allows the equivalent sound absorption area,  $A_i$ , to be determined for each partial area:

$$A_i = \alpha_i \times S_i \text{ (m}^2\text{)}$$

The total equivalent sound absorption area, A, is calculated by adding up the individual amounts:

$$A_{\text{total}} = \alpha_1 \times S_1 \text{ (m}^2\text{)} + \alpha_2 \times S_2 \text{ (m}^2\text{)} + \dots$$

## Reverberation time

The reverberation time,  $T_{60}$ , is a measure of the time required for the sound pressure to reduce to  $1/1000$  of its initial value after the sound source becomes silent.

This value is usually determined for a centre frequency (500 Hz or 1000 Hz) and specified accordingly.

The reverberation time increases in proportion to the volume of the room and in inverse proportion to the equivalent sound absorption area, A.

## Sabine formula

In the field of technical acoustics, reverberation time T is calculated with the "Sabine formula":

$$T = V \div A \times 0.163$$

"V" describes the room volume and "A" the equivalent sound absorption area in  $\text{m}^2$ .

## What do abbreviations

$\alpha_s$ ,  $\alpha_p$ ,  $\alpha_w$  and NRC A stand for?

$\alpha_s$  ( $\alpha_{s,1}$ ) describes the so-called **one-third-octave** value. In a close spacing of thirds, 18 different sound absorption values are measured between 100 and 5000 Hz (100 Hz, 125 Hz, 160 Hz, 200 Hz, 250 Hz, 315 Hz, 400 Hz, 500 Hz, 630 Hz, 800 Hz, 1000 Hz, 1250 Hz, 1600 Hz, 2000 Hz, 2500 Hz, 3150 Hz, 4000 Hz and 5000 Hz). A value of 1.0 means complete absorption, while a value of 0.0 means complete reflection.

$\alpha_p$  ( $\alpha_{p,1}$ ) describes the so-called **practical sound absorption coefficient**.

Three one-third-octave values  $\alpha_s$  are used to calculate an **octave value**  $\alpha_p$ . In addition 6 frequencies are represented (125 Hz, 250 Hz, 500 Hz, 1000 Hz, 2000 Hz and 4000 Hz).

$\alpha_w$  ( $\alpha_{w,1}$ ) describes the so-called **weighted sound absorption coefficient**. This is frequency-dependent and specified as a single-number value rounded to the nearest 0.05. The  $\alpha_w$  value can be supplemented with so-called "shape indicators". These state that the measured values in the low (L), mid (M) or high (H) frequency range are better than those identified by the  $\alpha_w$  value (see index word "shape indicators").

**NRC A** specifies the average of the sound absorption at octave values 250 Hz, 500 Hz, 1000 Hz and 2000 Hz, rounded to the nearest 0.05. A noise reduction coefficient of 0.80 stands for an average sound absorption of 80%.

## Shape indicators (L/M/H)

The weighted sound absorption coefficient,  $\alpha_w$ , can be supplemented with so-called "shape indicators", expressed by the letters L, M and H (low, mid, high), in which frequency ranges the sound absorption level is particularly high.

L Particularly good absorption up to 250 Hz

M Particularly good absorption at 500 Hz to 1000 Hz

H Particularly good absorption at 2000 Hz to 4000 Hz

## Absorber classes

According to DIN EN 11654, acoustic elements are assigned to absorber class A, B, C, D or E based on their sound absorption coefficient.

A Extremely absorbent

$\alpha_w$  0.90–1.00

B Highly absorbent

$\alpha_w$  0.80–0.85

C Very absorbent

$\alpha_w$  0.60–0.75

D Absorbent

$\alpha_w$  0.30–0.55

E Slightly absorbent

$\alpha_w$  0.15–0.25

## Longitudinal sound insulation $D_{n,f,w}$

In buildings with a skeleton construction – typically nearly all new office buildings today – the individual rooms are separated by lightweight partition walls. The ceilings are suspended.



The cavity that this creates between raw ceiling and suspended ceiling acts as a sound transmission path which must be compensated for with longitudinal sound insulation.

The longitudinal sound insulation can be implemented with vertical or horizontal compartmentalisation.

The longitudinal sound insulation is determined according to EN ISO 717-1 and specified as a weighted normalised flanking sound level difference  $D_{n,f,w}$  in dB units.

Here " $D_{n,f}$ " describes the normalised flanking level difference for flanking components (e.g. suspended ceilings). " $w$ " means that the measured values have been weighted in accordance with normative specifications. The specified numerical value is the value read from the reference curve at 500 Hz.


The reference curve is not shown in the test report diagrams.



## Perforation sizing

- A Horizontal spacing
- B Vertical spacing
- C Diagonal spacing 45°
- D Offset spacing 60°

# PRACTICAL EXAMPLE



## School construction

In common with many other schools, Gmunden Polytechnic School had huge problems with the acoustics in its classrooms. The effects were evident in restless students and overburdened teachers.


The initial situation was assessed analytically by building physicists and suggestions for improvement were developed methodically.

With metal acoustic ceilings and metal acoustic walls from Fural, it was possible to achieve huge improvements in room acoustics.

At the same time, the visual appearance of the equipped classrooms was significantly improved with the precisely prefabricated fittings.

## Reverberation time


The reverberation time is the best known room acoustic criterion. It is defined as the time in which the sound pressure level decreases by 60 dB after switching off the sound source. In the practical example of Gmunden Polytechnic School, the average reverberation time improved from ~ 1.7 s to the 0.6 s required by DIN 18041.



— Reverberant ceiling and wall  
— Acoustic metal ceiling with perforation Rg 2.5 – 16% and acoustic wall cladding with perforation Rg 0.7 – 1%  
■ Normal range


## D50 definition

The so-called "D50 definition" is a key room acoustics parameter. The larger the value, the more clearly the sound signal is perceived. In order to ensure good speech intelligibility, this value should be greater than 50%.




## The speaker is not understood.

The acoustic analysis of the situation before project start shows that speech intelligibility was below standard practically in the entire room.




## The speaker is understood in the entire room.

After installing the acoustic metal ceiling Fural Rg 2.5 – 16% and acoustic wall cladding Fural Rg 0.7 – 1%, speech intelligibility rose in the entire room to values between 70 and 98%. The values achieved are much higher than standard.




# METAL CEILINGS 1

Tissot Arena, Biel




<b>Fural</b>	
Perforation Ø	Rg 0.7-1%
0.7 mm	
Hole content	1 %
Max. perforation width	1,197 mm
Des. acc. to DIN 24041	Rg 0.70 - 6.00
Horizontal spacing	6.00 mm →
Vertical spacing	6.00 mm ↓
Diagonal spacing	8.48 mm ↘
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 231/2007
NRC	0.65
$\alpha_w$	0.50 (LM)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o

<b>Fural</b>	
Perforation Ø	Rg 0.7-1.5%
0.7 mm	
Hole content	1.5 %
Max. perforation width	1,400 mm
Des. acc. to DIN 24041	Rg 0.70 - 5.00
Horizontal spacing	5.00 mm →
Vertical spacing	5.00 mm ↓
Diagonal spacing	7.07 mm ↘
Perforation direction	→



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 231/2007
NRC	0.60
$\alpha_w$	0.50 (L)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o




<b>Fural</b>	
Perforation Ø	Rg 0.7-4%
0.7 mm	
Hole content	4 %
Max. perforation width	1,197 mm
Des. acc. to DIN 24041	Rg 0.70 - 3.00
Horizontal spacing	3.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↘
Perforation direction	→



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 219/2007
NRC	0.80
$\alpha_w$	0.75 (L)
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o


# METAL CEILINGS 2

Training centre, Berne




	Fural
Perforation Ø	Rg 0.8 - 6%
0.8 mm	
Hole content	6 %
Max. perforation width	1,400 mm
Des. acc. to DIN 24041	Rg 0.80 - 3.00
Horizontal spacing	3.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↓
Perforation direction	→

	Fural
Perforation Ø	Rd 0.8 - 11%
0.8 mm	
Hole content	11 %
Max. perforation width	1,400 mm
Des. acc. to DIN 24041	Rd 0.80 - 2.12
Horizontal spacing	3.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↓
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	09.06.2017 M 105629/17
NRC	0.75
$\alpha_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

	Fural
Perforation Ø	Rg 0.9 - 7%
0.9 mm	
Hole content	7 %
Max. perforation width	1,020 mm
Des. acc. to DIN 24041	Rg 0.90 - 3.00
Horizontal spacing	3.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↓
Perforation direction	→







Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	09.06.2017 M 105629/18
NRC	0.75
$\alpha_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

	Fural
Perforation Ø	Rd 0.9 - 14 %
0.9 mm	
Hole content	14 %
Max. perforation width	1,020 mm
Des. acc. to DIN 24041	Rd 0.90 - 2.12
Horizontal spacing	3.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↓
Perforation direction	→




Overall structure	400 mm
Fleece	Bonded acoustic fleece
Test certificate	17.11.2012 7178-12-2
NRC	0.55
$\alpha_w$	0.55 (LH)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o

# METAL CEILINGS 3




<b>Fural</b>	
Perforation Ø	Rd 1.5 - 11%
1.5 mm	
Hole content	11%
Max. perforation width	1,488 mm
Des. acc. to DIN 24041	Rg 1.50 - 4.00
Horizontal spacing	4.00 mm →
Vertical spacing	4.00 mm ↓
Diagonal spacing	5.65 mm ↘
Perforation direction	→

**Sound absorption**



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/6
NRC	0.80
$\alpha_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

<b>Fural</b>	
Perforation Ø	Rd 1.5 - 11%
1.5 mm	
Hole content	11%
Max. perforation width	1,470 mm
Des. acc. to DIN 24041	Rd 1.50 - 4.00
Horizontal spacing	5.66 mm →
Vertical spacing	2.83 mm ↓
Diagonal spacing	4.00 mm ↘
Perforation direction	→

**Sound absorption**







Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/6
NRC	0.80
$\alpha_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

<b>Fural</b>	
Perforation Ø	Rd 1.5 - 22%
1.5 mm	
Hole content	22%
Max. perforation width	1,488 mm
Des. acc. to DIN 24041	Rd 1.50 - 2.83
Horizontal spacing	4.00 mm →
Vertical spacing	2.00 mm ↓
Diagonal spacing	2.83 mm ↘
Perforation direction	→


**Sound absorption**


Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/5
NRC	0.70
$\alpha_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

# METAL CEILINGS 4



<b>Fural</b>	
Rv 1.6 - 20 %	
Perforation Ø 1.6 mm	
Hole content 20 %	
Max. perforation width 1,450 mm	
Des. acc. to DIN 24041	
Horizontal spacing 3.50 mm →	
Vertical spacing 3.03 mm ↓	
Offset spacing 60°	
Perforation direction →	



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 2
NRC	0.75
$\alpha_w$	0.80
Absorber class	B (DIN EN 11654)
Acoustic infill	w/o



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	09.06.2017 M 105629/19
NRC	0.70
$\alpha_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/4
NRC	0.80
$\alpha_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o


Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/4
NRC	0.80
$\alpha_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

# METAL CEILINGS 5

Terminal 3, Vienna Airport




<b>Fural</b>	
Rg 1.8 - 20 %	
Perforation Ø	1.8 mm
Hole content	20 %
Max. perforation width	1.460 mm
Des. acc. to DIN 24041	Rg 1.80 - 3.50
Horizontal spacing	3.50 mm →
Vertical spacing	3.50 mm ↓
Diagonal spacing	4.95 mm ↘
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 220/2007 Figure 2
NRC	0.75
$a_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o


<b>Fural</b>	
Rd 1.8 - 21 %	
Perforation Ø	1.8 mm
Hole content	21 %
Max. perforation width	1.400 mm
Des. acc. to DIN 24041	Rd 1.80 - 3.50
Horizontal spacing	4.96 mm →
Vertical spacing	2.48 mm ↓
Diagonal spacing	3.50 mm ↘
Perforation direction	→



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 220/2007 Figure 2
NRC	0.75
$a_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o




<b>Fural</b>	
Rd 2.5 - 8 %	
Perforation Ø	2.5 mm
Hole content	8 %
Max. perforation width	1.460 mm
Des. acc. to DIN 24041	Rd 2.50 - 7.80
Horizontal spacing	11.0 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→








Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 5
NRC	0.80
$a_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

<b>Fural</b>	
Rg 2.5 - 16 %	
Perforation Ø	2.5 mm
Hole content	16 %
Max. perforation width	1.460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 1
NRC	0.80
$a_w$	0.80
Absorber class	B (DIN EN 11654)
Acoustic infill	w/o

# METAL CEILINGS 6




	Fural
Perforation Ø	Rd 2.5 - 23%
Hole content	2.5 mm
Max. perforation width	23 %
Des. acc. to DIN 24041	1.467 mm
Horizontal spacing	Rv 2.50 - 5.00
Vertical spacing	8.66 mm →
Offset spacing 60°	2.50 mm ↓
Perforation direction	5.00 mm ↓
→	5.00 mm ↓




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/7
NRC	0.75
$\alpha_w$	0.75 (L)
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

	Fural
Perforation Ø	Rd 2.8 - 20%
Hole content	2.8 mm
Max. perforation width	20 %
Des. acc. to DIN 24041	627.9 mm
Horizontal spacing	Rd 2.80 - 5.50
Vertical spacing	8.66 mm →
Offset spacing 60°	7.80 mm →
Perforation direction	3.90 mm ↓
→	5.50 mm ↓




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	09.06.2017 M 105629/20
NRC	0.75
$\alpha_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

	Fural
Perforation Ø	Rg 3.0 - 12%
Hole content	3.0mm
Max. perforation width	12 %
Des. acc. to DIN 24041	877.5 mm
Horizontal spacing	Rg 3.00 - 7.50
Vertical spacing	7.50 mm →
Diagonal spacing	7.50 mm ↓
Perforation direction	10.6 mm ↘
→	→



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	30.09.2019 M 105629/43
NRC	0.75
$\alpha_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o


	Fural
Perforation Ø	Rd 3.0 - 24%
Hole content	3.0mm
Max. perforation width	24 %
Des. acc. to DIN 24041	877.5 mm
Horizontal spacing	Rd 3.00 - 5.30
Vertical spacing	7.50 mm →
Diagonal spacing	3.75 mm ↓
Perforation direction	5.30 mm ↘
→	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	30.09.2019 M 105629/45
NRC	0.70
$\alpha_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

# METAL CEILINGS 7

Schuler AG, Göppingen




<b>Fural</b>	
Perforation Ø	Rg 3,0 - 20 %
3,0 mm	
Hole content	20 %
Max. perforation width	1.434 mm
Des. acc. to DIN 24041	Rg 3,00 - 6,00
Horizontal spacing	6,00 mm →
Vertical spacing	6,00 mm ↓
Diagonal spacing	8,48 mm ↓
Perforation direction	→





Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 221/2007 Figure 2
NRC	0,80
$\alpha_w$	0,75 [L]
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o


<b>Fural</b>	
Perforation Ø	Rv 3,0 - 20 %
3,0 mm	
Hole content	20 %
Max. perforation width	1.402 mm
Des. acc. to DIN 24041	Rv 3,00 - 6,35
Horizontal spacing	6,50 mm →
Vertical spacing	5,50 mm ↓
Offset spacing	6,39 mm ↓
Perforation direction	→



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 221/2007 Figure 2
NRC	0,80
$\alpha_w$	0,75 [L]
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o




<b>Fural</b>	
Perforation Ø	Rd 4,0 - 6 %
4,0 mm	
Hole content	6 %
Max. perforation width	680 mm
Des. acc. to DIN 24041	Rd 4,00 - 14,14
Horizontal spacing	20,00 mm →
Vertical spacing	10,00 mm ↓
Diagonal spacing	14,14 mm ↓
Perforation direction	→



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	30.09.2019 M 105629/46
NRC	0,65
$\alpha_w$	0,65
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

<b>Fural</b>	
Perforation Ø	Rg 4,0 - 12 %
4,0 mm	
Hole content	12 %
Max. perforation width	680 mm
Des. acc. to DIN 24041	Rg 4,00 - 10,00
Horizontal spacing	10,00 mm →
Vertical spacing	10,00 mm ↓
Diagonal spacing	14,14 mm ↓
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	30.09.2019 M 105629/48
NRC	0,75
$\alpha_w$	0,75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o


# METAL CEILINGS 8




Verlagsanstalt Handwerk, Düsseldorf




**Fural**  
Rg 4.0 - 17%  
Perforation Ø 4.0 mm  
Hole content 17%  
Max. perforation width 1,453 mm  
Des. acc. to DIN 24041  
Horizontal spacing 8.60 mm →  
Vertical spacing 8.60 mm ↓  
Diagonal spacing 12.1 mm ↘  
Perforation direction →

**Sound absorption**



Overall structure 200 mm  
Fleece Bonded acoustic fleece  
Test certificate P-BA 279/2006 Figure 7  
NRC 0.80  
 $a_w$  0.80  
Absorber class B (DIN EN 11654)  
Acoustic infill w/o




**Fural**  
Rd 4.0 - 33%  
Perforation Ø 4.0 mm  
Hole content 33%  
Max. perforation width 1,450 mm  
Des. acc. to DIN 24041  
Horizontal spacing 8.60 mm →  
Vertical spacing 4.30 mm ↓  
Diagonal spacing 6.10 mm ↘  
Perforation direction →

**Sound absorption**

Overall structure 200 mm  
Fleece Bonded acoustic fleece  
Test certificate P-BA 279/2006 Figure 3  
NRC 0.80  
 $a_w$  0.80  
Absorber class B (DIN EN 11654)  
Acoustic infill w/o




**Fural**  
Qg 4.0 - 33%  
Perforation 4.0 mm  
Hole content 33%  
Max. perforation width 630 mm  
Des. acc. to DIN 24041  
Horizontal spacing 7.00 mm →  
Vertical spacing 7.00 mm ↓  
Diagonal spacing 9.89 mm ↘  
Perforation direction →

**Sound absorption**

Overall structure 200 mm  
Fleece Bonded acoustic fleece  
Test certificate P-BA 279/2006 Figure 4  
NRC 0.80  
 $a_w$  0.80  
Absorber class B (DIN EN 11654)  
Acoustic infill w/o


# METAL CEILINGS 9

Petrom City, Bucharest





**Fural**  
Rv 4.5 - 51%  
Perforation Ø 4.5 mm  
Hole content 51%  
Max. perforation width 627 mm  
Des. acc. to DIN 24041  
Horizontal spacing 10.4 mm →  
Vertical spacing 3.00 mm ↓  
Offset spacing 60° 6.00 mm ↓  
Perforation direction →

#### Sound absorption




Overall structure 200 mm  
Fleece Bonded acoustic fleece  
Test certificate 09.06.2017 M105629/21  
NRC 0.65  
 $a_w$  0.65 [L]  
Absorber class C (DIN EN 11654)  
Acoustic infill w/o




**Fural**  
Rg 14.0 - 23%  
Perforation Ø 14.0 mm  
Hole content 23%  
Max. perforation width 598 mm  
Des. acc. to DIN 24041  
Horizontal spacing 26.0 mm →  
Vertical spacing 26.0 mm ↓  
Diagonal spacing 36.7 mm ↘  
Perforation direction →

#### Sound absorption




Overall structure 200 mm  
Fleece Bonded acoustic fleece  
Test certificate P-BA 279/2006 Figure 8  
NRC 0.75  
 $a_w$  0.75 [L]  
Absorber class C (DIN EN 11654)  
Acoustic infill w/o


# EFFECT OF THE AIR CAVITY





Fural	
Perforation Ø	Rg 2.5 - 16 %
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↓
Perforation direction	→



Overall structure	50mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 20
NRC	0.65; <b>0.90</b>
$a_w$	0.50 (MH); <b>0.80</b>
Absorber class	B (DIN EN 11654), <b>A</b> (DIN EN 11654)
Acoustic infill	30 mm mineral wool 45 kg/m³




Overall structure	100 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 21
NRC	0.75; <b>0.95</b>
$a_w$	0.80; <b>0.95</b>
Absorber class	B (DIN EN 11654), <b>A</b> (DIN EN 11654)
Acoustic infill	30 mm mineral wool 45 kg/m³




## Air cavity and sound absorption coefficient


The sound absorption coefficient depends not only on the perforation used in the metal ceiling, but also and in particular on the air cavity. Here is a comparison of four different installation heights (50, 100, 200 and 400 mm).




Fural	
Perforation Ø	Rg 2.5 - 16 %
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↓
Perforation direction	→




Overall structure	200mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 1
NRC	0.80; <b>0.95</b>
$a_w$	0.80; <b>0.95</b>
Absorber class	B (DIN EN 11654), <b>A</b> (DIN EN 11654)
Acoustic infill	30 mm mineral wool 45 kg/m³



Fural	
Perforation Ø	Rg 2.5 - 16 %
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↓
Perforation direction	→





Overall structure	400mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 22
NRC	0.75; <b>0.90</b>
$a_w$	0.75 (L); <b>0.90</b>
Absorber class	C (DIN EN 11654), <b>A</b> (DIN EN 11654)
Acoustic infill	30 mm mineral wool 45 kg/m³



# EFFECT OF ACOUSTIC INFILLS 1



SKA Rehabilitation Centre, St. Radegund




## Different acoustic infills (absorber types)

The sound absorption coefficient is greatly affected by the acoustic infills used, which can consist of mineral wool, mineral wool sealed in PE film, foam or polyester wool.

These acoustic infills are also available in different volumetric weights ( $\text{kg/m}^3$ ).


	Fural
Rg 2.5 - 16 %	
Perforation Ø 2.5 mm	
Hole content 16 %	
Max. perforation width 1,460 mm	
Des. acc. to DIN 24041	
Horizontal spacing 5.50 mm →	
Vertical spacing 5.50 mm ↓	
Diagonal spacing 7.78 mm ↘	
Perforation direction →	



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 14
NRC	0.95
$a_w$	0.95
Absorber class	A [DIN EN 11654]

**Acoustic infill** 30 mm mineral wool 45 kg/m<sup>3</sup>


	Fural
Rg 2.5 - 16 %	
Perforation Ø 2.5 mm	
Hole content 16 %	
Max. perforation width 1,460 mm	
Des. acc. to DIN 24041	
Horizontal spacing 5.50 mm →	
Vertical spacing 5.50 mm ↓	
Diagonal spacing 7.78 mm ↘	
Perforation direction →	



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 17
NRC	0.85
$a_w$	0.90
Absorber class	A [DIN EN 11654]


**Acoustic infill** 30 mm mineral wool 45 kg/m<sup>3</sup> in PE film

	Fural
Rg 2.5 - 16 %	
Perforation Ø 2.5 mm	
Hole content 16 %	
Max. perforation width 1,460 mm	
Des. acc. to DIN 24041	
Horizontal spacing 5.50 mm →	
Vertical spacing 5.50 mm ↓	
Diagonal spacing 7.78 mm ↘	
Perforation direction →	





Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 18
NRC	0.95
$a_w$	0.95
Absorber class	A [DIN EN 11654]

**Acoustic infill** 30 mm foam 9 kg/m<sup>3</sup>





Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 19
NRC	0.95
$a_w$	0.95
Absorber class	A [DIN EN 11654]

**Acoustic infill** 30 mm polyester wool 48 g/m<sup>3</sup>



# EFFECT OF ACOUSTIC INFILLS 2

Sixth-Form Centre, Horw




## Different acoustic infills (absorber types)

The sound absorption coefficient is greatly affected by the acoustic infills used, which can consist of mineral wool, mineral wool sealed in PE film, foam or polyester wool.

These acoustic infills are also available in different volumetric weights ( $\text{kg/m}^3$ ).


<b>Fural</b>	
Rg 0.7 - 4 %	
Perforation Ø 0.7 mm	Rd 1.5 - 22 %
Hole content 4 %	1.5 mm
Max. perforation width 1,197 mm	Hole content 22 %
Des. acc. to DIN 24041	Max. perforation width 1,488 mm
Horizontal spacing 3.00 mm →	Des. acc. to DIN 24041 Rd 1.50 - 2.83
Vertical spacing 3.00 mm ↓	Horizontal spacing 4.00 mm →
Diagonal spacing 4.24 mm ↘	Vertical spacing 2.00 mm ↓
Perforation direction →	Diagonal spacing 2.83 mm ↘



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	04.07.2017 M105629/22
NRC	0.75
$a_w$	0.75
Absorber class	C (DIN EN 11654)

**Acoustic infill** 20 mm mineral wool 45 kg/m<sup>3</sup> in PE film


<b>Fural</b>	
Perforation Ø 1.5 mm	Rd 1.5 - 22 %
Hole content 22 %	1.5 mm
Max. perforation width 1,488 mm	Horizontal spacing 4.00 mm →
Des. acc. to DIN 24041	Vertical spacing 2.00 mm ↓
Horizontal spacing 4.00 mm →	Diagonal spacing 2.83 mm ↘
Vertical spacing 2.00 mm ↓	Perforation direction →
Diagonal spacing 2.83 mm ↘	
Perforation direction →	



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	05.07.2017 M105629/26
NRC	0.85
$a_w$	0.90
Absorber class	A (DIN EN 11654)

**Acoustic infill** 20 mm mineral wool 45 kg/m<sup>3</sup> in PE film


<b>Fural</b>	
Perforation Ø 1.5 mm	Rd 1.5 - 22 %
Hole content 22 %	1.5 mm
Max. perforation width 1,488 mm	Horizontal spacing 4.00 mm →
Des. acc. to DIN 24041	Vertical spacing 2.00 mm ↓
Horizontal spacing 4.00 mm →	Diagonal spacing 2.83 mm ↘
Vertical spacing 2.00 mm ↓	Perforation direction →
Diagonal spacing 2.83 mm ↘	
Perforation direction →	



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	04.12.2019 M105629
NRC	0.70
$a_w$	0.70
Absorber class	C (DIN EN 11654)



**Acoustic infill** 15 mm mineral fibreboard 300 kg/m<sup>3</sup>

<b>Fural</b>	
Perforation Ø 1.5 mm	Rd 1.5 - 22 %
Hole content 22 %	1.5 mm
Max. perforation width 1,488 mm	Horizontal spacing 4.00 mm →
Des. acc. to DIN 24041	Vertical spacing 2.00 mm ↓
Horizontal spacing 4.00 mm →	Diagonal spacing 2.83 mm ↘
Vertical spacing 2.00 mm ↓	Perforation direction →
Diagonal spacing 2.83 mm ↘	
Perforation direction →	



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	04.12.2019 M105629
NRC	0.60
$a_w$	0.60
Absorber class	C (DIN EN 11654)

**Acoustic infill** 20 mm mineral fibreboard 320 kg/m<sup>3</sup>





This structure can also be found analogously in the longitudinal sound insulation chapter.

This structure can also be found analogously in the longitudinal sound insulation chapter.

# EFFECT OF THE ACOUSTIC INFILL THICKNESS


Klinikum Nord, Nuremberg



Different acoustic infill thicknesses (absorber thicknesses)


The acoustic infill thickness affects the sound absorption coefficient just as much as the acoustic infill type and the height of the air cavity. All of these 3 factors play an important role in the acoustic behaviour of the metal ceiling.

Fural	
Rg 2.5 - 16 %	
Perforation Ø	2.5 mm
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 13
NRC	0.95
$a_w$	0.95
Absorber class	A [DIN EN 11654]
<b>Acoustic infill</b>	<b>20 mm mineral wool 45 kg/m³</b>

Fural	
Rg 2.5 - 16 %	
Perforation Ø	2.5 mm
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 14
NRC	0.95
$a_w$	0.95
Absorber class	A [DIN EN 11654]
<b>Acoustic infill</b>	<b>30 mm mineral wool 45 kg/m³</b>

Fural	
Rg 2.5 - 16 %	
Perforation Ø	2.5 mm
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→







Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 15
NRC	0.95
$a_w$	1.00
Absorber class	A [DIN EN 11654]
<b>Acoustic infill</b>	<b>40 mm mineral wool 45 kg/m³</b>

Fural	
Rg 2.5 - 16 %	
Perforation Ø	2.5 mm
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→





Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 279/2006 Figure 16
NRC	1.00
$a_w$	1.00
Absorber class	A [DIN EN 11654]
<b>Acoustic infill</b>	<b>50 mm mineral wool 45 kg/m³</b>



# EFFECT OF THE ACOUSTIC FLEECE

Apothekerhaus, Vienna





Overall structure	200 mm
<b>Fleece</b>	<b>w/o</b>
Test certificate	P-BA 222/2007 Figure 2
NRC	0.45
$\alpha_w$	0.35 (L)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o



# EFFECT OF HEAVY-DUTY ACOUSTIC INFILLS 1

Military hospital, Ulm





## Heavy-duty acoustic infills


Using heavy-duty acoustic infills in metal ceiling systems can significantly improve the longitudinal sound insulation – the acoustic transmission between two adjacent rooms separated by walls.

## Longitudinal sound insulation


Acoustic metal ceilings with acoustic infill and heavy-duty acoustic infill are used preferentially for longitudinal sound insulation. See also pages 78–79 of this brochure.

Fural		Fural		Fural		Fural	
Perforation Ø	Rg 0.7 - 4 % 0.7 mm 4 % Max. perforation width Des. acc. to DIN 24041 Horizontal spacing Vertical spacing Diagonal spacing Perforation direction	Perforation Ø	Rg 0.7 - 4 % 0.7 mm 4 % Max. perforation width Des. acc. to DIN 24041 Horizontal spacing Vertical spacing Diagonal spacing Perforation direction	Perforation Ø	Rd 1.5 - 22 % 1.5 mm 22 % Max. perforation width Des. acc. to DIN 24041 Horizontal spacing Vertical spacing Diagonal spacing Perforation direction	Perforation Ø	Rd 1.5 - 22 % 1.5 mm 22 % Max. perforation width Des. acc. to DIN 24041 Horizontal spacing Vertical spacing Diagonal spacing Perforation direction
<b>Sound absorption</b>	Sound absorption coefficient $\alpha_s$ at one-third centre frequency f [Hz]	<b>Sound absorption</b>	Sound absorption coefficient $\alpha_s$ at one-third centre frequency f [Hz]	<b>Sound absorption</b>	Sound absorption coefficient $\alpha_s$ at one-third centre frequency f [Hz]	<b>Sound absorption</b>	Sound absorption coefficient $\alpha_s$ at one-third centre frequency f [Hz]
Overall structure	200 mm	Overall structure	200 mm	Overall structure	200 mm	Overall structure	200 mm
Fleece	Bonded acoustic fleece	Fleece	Bonded acoustic fleece	Fleece	Bonded acoustic fleece	Fleece	Bonded acoustic fleece
Test certificate	04.07.2017 M105629/24	Test certificate	04.07.2017 M105629/25	Test certificate	05.07.2017 M105629/28	Test certificate	05.07.2017 M105629/29
NRC	0.75	NRC	0.70	NRC	0.75	NRC	0.75
$\alpha_w$	0.65 (M)	$\alpha_w$	0.60 (M)	$\alpha_w$	0.60 (MH)	$\alpha_w$	0.65 (M)
Absorber class	C (DIN EN 11654)	Absorber class	C (DIN EN 11654)	Absorber class	C (DIN EN 11654)	Absorber class	C (DIN EN 11654)
<b>Acoustic infill</b>	20 mm mineral wool 28 kg/m³ in PE film + 12.5 mm plasterboard	<b>Acoustic infill</b>	20 mm mineral wool 28 kg/m³ in PE film + cooling system + 12.5 mm plasterboard	<b>Acoustic infill</b>	20 mm mineral wool 28 kg/m³ in PE film + 12.5 mm plasterboard	<b>Acoustic infill</b>	20 mm mineral wool 28 kg/m³ in PE film + cooling system + 12.5 mm plasterboard






<b>Fural</b>
Rg 2.5 - 16 %
Perforation Ø 2.5 mm
Hole content 16 %
Max. perforation width 1,460 mm
Des. acc. to DIN 24041
Horizontal spacing 5.50 mm →
Vertical spacing 5.50 mm ↓
Diagonal spacing 7.78 mm ↘
Perforation direction →




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 229/2007 Figure 2
NRC	0.80
$\alpha_w$	0.85
Absorber class	B [DIN EN 11654]
<b>Acoustic infill</b>	<b>50 mm mineral wool 28 kg/m³ in PE film + 1 mm sheet steel</b>



<b>Fural</b>
Rg 2.5 - 16 %
Perforation Ø 2.5 mm
Hole content 16 %
Max. perforation width 1,460 mm
Des. acc. to DIN 24041
Horizontal spacing 5.50 mm →
Vertical spacing 5.50 mm ↓
Diagonal spacing 7.78 mm ↘
Perforation direction →



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 227/2007 Figure 2
NRC	0.75
$\alpha_w$	0.80
Absorber class	C [DIN EN 11654]
<b>Acoustic infill</b>	<b>50 mm mineral wool 28 kg/m³ in PE film + 12.5 mm plasterboard</b>



#### Heavy-duty acoustic infills

Using heavy-duty acoustic infills in metal ceiling systems can significantly improve the longitudinal sound insulation – the acoustic transmission between two adjacent rooms separated by walls.

#### Longitudinal sound insulation

Acoustic metal ceilings with acoustic infill and heavy-duty acoustic infill are used preferentially for longitudinal sound insulation. See also pages 78–79 of this brochure.


# SILENCE

"One is always active with a certain amount of noise.  
Work takes place in silence."  
(Peter Bamm, 1897–1975)


Bison Offices, Sursee  
- Leuenberger Architects  
- Offices  
- Perforation Rd 1.5 – 22 %  
- Colour RAL 9016 traffic white  
- Hang-in system H28

# EXPANDED METAL CEILINGS

District council building, Kirchdorf



Fural	
Free cross-section	16.0×8.0×1.5×1.0
Max. width	63%
L [diagonal 1]	1,140 mm
W [diagonal 2]	16.0 mm →
B (web width)	8.0 mm ↓
A (web thickness)	1.5 mm
A (web thickness)	




Overall structure	50 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 246/2002 Figure 5
NRC	0.40
$\alpha_w$	0.40 (MH)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o

Overall structure	100 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 246/2002 Figure 6
NRC	0.70
$\alpha_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o


Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 246/2002 Figure 1
NRC	0.70
$\alpha_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

Overall structure	400 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 246/2002 Figure 7
NRC	0.70
$\alpha_w$	0.70 (LH)
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o




## Air cavity and sound absorption coefficient

From a free cross-section > 70%, the sound absorption coefficient is hardly affected by the mesh size, but rather and in particular by the fleece, the acoustic infill and the air cavity.





Fural	
Free cross-section	16.0×8.0×1.5×1.0
Max. width	63%
L [diagonal 1]	1,140 mm
W [diagonal 2]	16.0 mm →
B (web width)	8.0 mm ↓
A (web thickness)	1.5 mm
A (web thickness)	




Overall structure	400 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 246/2002 Figure 7
NRC	0.70
$\alpha_w$	0.70 (LH)
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o

# EFFECT OF ACOUSTIC INFILLS

District council building, Kirchdorf




Fural	
16.0×8.0×1.5×1.0	
Free cross-section	63%
Max. width	1,140 mm
L [diagonal 1]	16.0 mm →
W [diagonal 2]	8.0 mm ↓
B (web width)	1.5 mm
A (web thickness)	1.0 mm




Overall structure	200 mm
Fleece	-
Test certificate	04.12.2019 M105629
NRC	0.40
$\alpha_w$	0.45 (H)
Absorber class	D (DIN EN 11654)
<b>Acoustic infill</b>	<b>10 mm polyester wool 35 kg/m³</b>

Fural	
16.0×8.0×1.5×1.0	
Free cross-section	63%
Max. width	1,140 mm
L [diagonal 1]	16.0 mm →
W [diagonal 2]	8.0 mm ↓
B (web width)	1.5 mm
A (web thickness)	1.0 mm






Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 246/2002 Figure 2
NRC	1.00
$\alpha_w$	1.00 (MH)
Absorber class	A (DIN EN 11654)
<b>Acoustic infill</b>	<b>30 mm mineral wool 45 kg/m³</b>




## Air cavity and sound absorption coefficient


From a free cross-section > 70%, the sound absorption coefficient is hardly affected by the mesh size, but rather and in particular by the fleece, the acoustic infill and the air cavity.



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 246/2002 Figure 3
NRC	0.90
$\alpha_w$	0.90
Absorber class	A (DIN EN 11654)
<b>Acoustic infill</b>	<b>30 mm mineral wool 45 kg/m³ in PE film</b>





Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 246/2002 Figure 4
NRC	1.00
$\alpha_w$	1.00
Absorber class	A (DIN EN 11654)
<b>Acoustic infill</b>	<b>30 mm polyester wool 48 g/m³</b>






# COOLING CEILINGS 1




	<b>Fural</b>
Perforation Ø	Rg 0.7 - 4 %
Hole content	0.7 mm
Max. perforation width	4 %
Des. acc. to DIN 24041	1,140 mm
Horizontal spacing	Rg 0.70 - 3.00
Vertical spacing	3.0 mm →
Diagonal spacing	3.0 mm ↓
Perforation direction	4.42 mm ↓
→	




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 225/2007
NRC	0.85
$a_w$	0.65 (LM)
Absorber class	C (DIN EN 11654)
<b>Acoustic infill</b>	30 mm mineral wool 28kg/m³ in PE film + cooling system
<b>Acoustic occ. level</b>	31% (cooling system + 4 heat conducting profiles)




	<b>Fural</b>
Perforation Ø	Rg 2.5 - 16 %
Hole content	2.5mm
Max. perforation width	16 %
Des. acc. to DIN 24041	1,140 mm
Horizontal spacing	Rg 2.50 - 5.50
Vertical spacing	3.0mm →
Diagonal spacing	5.5mm →
Perforation direction	5.5mm ↓
→	




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 223/2007
NRC	0.90
$a_w$	0.80
Absorber class	B (DIN EN 11654)
<b>Acoustic infill</b>	30 mm mineral wool 28kg/m³ in PE film + cooling system
<b>Acoustic occ. level</b>	31% (cooling system + 4 heat conducting profiles)




**Acoustic occupancy level**  
Metal ceilings are particularly suitable for combination with water-bearing heat exchangers for room temperature control. Fitting the ceiling with cooling systems changes the acoustic properties of the ceiling panels, because the previously continuous holes of profiles are covered. Therefore the "acoustic occupancy level" is specified in the tables. This means the proportion of the area covered by the heat conducting profile.




	<b>Fural</b>
Perforation Ø	Rg 2.5 - 16 %
Hole content	2.5mm
Max. perforation width	16 %
Des. acc. to DIN 24041	1,140 mm
Horizontal spacing	Rg 2.50 - 5.50
Vertical spacing	5.5mm →
Diagonal spacing	5.5mm ↓
Perforation direction	7.78mm ↓
→	



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 224/2007 Figure 2
NRC	0.85
$a_w$	0.85
Absorber class	B (DIN EN 11654)
<b>Acoustic infill</b>	40mm mineral wool 28kg/m³ in PE film + cooling system + 12.5 mm plasterboard
<b>Acoustic occ. level</b>	31% (cooling system + 4 heat conducting profiles)



	<b>Fural</b>
Perforation Ø	Rg 2.5 - 16 %
Hole content	2.5mm
Max. perforation width	16 %
Des. acc. to DIN 24041	1,140 mm
Horizontal spacing	Rg 2.50 - 5.50
Vertical spacing	5.5mm →
Diagonal spacing	5.5mm ↓
Perforation direction	7.78mm ↓
→	




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 228/2007 Figure 2
NRC	0.85
$a_w$	0.85
Absorber class	B (DIN EN 11654)
<b>Acoustic infill</b>	40mm mineral wool 28kg/m³ in PE film + cooling system + 1.0 mm sheet steel
<b>Acoustic occ. level</b>	31% (cooling system + 4 heat conducting profiles)



# COOLING CEILINGS 2

Schunk Carbon Technology GmbH, Bad Goisern







	Fural
Perforation Ø	Rg 1.5 - 11%
Hole content	1.5 mm
Max. perforation width	11%
Des. acc. to DIN 24041	1,488 mm
Horizontal spacing	Rg 1.50 - 4.00
Vertical spacing	4.00 mm →
Diagonal spacing	4.00 mm ↓
Perforation direction	5.65 mm ↓
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz]
Overall structure	750 mm
Fleece	Bonded acoustic fleece
Test certificate	26.06.2014 M105629/10
NRC	0.75
$a_w$	0.80
Absorber class	B (DIN EN 11654)
Acoustic infill	30 mm mineral wool 45 kg/m³ in PE film + cooling system
Acoustic occ. level	47% (cooling system + 4 heat conducting profiles)

	Fural
Perforation Ø	Rg 1.5 - 11%
Hole content	1.5 mm
Max. perforation width	11%
Des. acc. to DIN 24041	1,488 mm
Horizontal spacing	Rg 1.50 - 4.00
Vertical spacing	4.00 mm →
Diagonal spacing	4.00 mm ↓
Perforation direction	5.65 mm ↓
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz]
Overall structure	750 mm
Fleece	Bonded acoustic fleece
Test certificate	26.06.2014 M105629/11
NRC	0.70
$a_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	30 mm mineral wool 45 kg/m³ in PE film + cooling system
Acoustic occ. level	59% (cooling system + 5 heat conducting profiles)

	Fural
Perforation Ø	Rg 1.5 - 11%
Hole content	1.5 mm
Max. perforation width	11%
Des. acc. to DIN 24041	1,488 mm
Horizontal spacing	Rg 1.50 - 4.00
Vertical spacing	4.00 mm →
Diagonal spacing	4.00 mm ↓
Perforation direction	5.65 mm ↓
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz]
Overall structure	750 mm
Fleece	Bonded acoustic fleece
Test certificate	28.04.2014 M105629/8
NRC	0.60
$a_w$	0.60
Absorber class	C (DIN EN 11654)
Acoustic infill	30 mm mineral wool 45 kg/m³ in PE film + cooling system
Acoustic occ. level	71% (cooling system + 6 heat conducting profiles)



	Fural
Perforation Ø	Rg 1.5 - 11%
Hole content	1.5 mm
Max. perforation width	11%
Des. acc. to DIN 24041	1,488 mm
Horizontal spacing	Rg 1.50 - 4.00
Vertical spacing	4.00 mm →
Diagonal spacing	4.00 mm ↓
Perforation direction	5.65 mm ↓
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz]
Overall structure	750 mm
Fleece	Bonded acoustic fleece
Test certificate	28.04.2014 M105629/9
NRC	0.65
$a_w$	0.60
Absorber class	C (DIN EN 11654)
Acoustic infill	80 mm mineral wool 30kg/m³ in PE film + cooling system
Acoustic occ. level	71% (cooling system + 6 heat conducting profiles)



**Acoustic occupancy level**  
Metal ceilings are particularly suitable for combination with water-bearing heat exchangers for room temperature control. Fitting the ceiling with cooling systems changes the acoustic properties of the ceiling panels, because the previously continuous holes of profiles are covered. Therefore the "acoustic occupancy level" is specified in the tables. This means the proportion of the area covered by the heat conducting profile.


# COOLING CEILINGS 3

Palazzo Regione Lombardia, Milan





	Fural
Perforation Ø	Rg 0.7 - 4 %
Hole content	0.7 mm
Max. perforation width	4 %
Des. acc. to DIN 24041	1,140 mm
Horizontal spacing	Rg 0.70 - 3.00
Vertical spacing	3.00 mm →
Diagonal spacing	3.00 mm ↓
Perforation direction	4.42 mm ↓
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz], <b>Fleece and cooling system plus mineral wool in PE</b>
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M61840/10 + <a href="#">M61840/8</a>
NRC	0.75; <b>0.90</b>
$a_w$	0.65 (LM); <b>0.80 (L)</b>
Absorber class	C (DIN EN 11654), B (DIN EN 11654)
Acoustic infill	<b>40 mm mineral wool 45 kg/m³ in PE film + Temperon cooling system</b>
Acoustic occ. level	29% [cooling system]

	Fural
Perforation Ø	Rv 1.6 - 20 %
Hole content	1.6 mm
Max. perforation width	20 %
Des. acc. to DIN 24041	1,450 mm
Horizontal spacing	Rv 1.60 - 3.50
Vertical spacing	3.50 mm →
Diagonal spacing	3.03 mm ↓
Perforation direction	Offset spacing 60°
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz], <b>Fleece and cooling system plus mineral wool in PE</b>
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M61840/9 + <a href="#">M61840/13</a>
NRC	0.70; <b>0.95</b>
$a_w$	0.65; <b>0.95</b>
Absorber class	C (DIN EN 11654), A (DIN EN 11654)
Acoustic infill	<b>40 mm mineral wool 45 kg/m³ in PE film + Temperon cooling system</b>
Acoustic occ. level	29% [cooling system]





**Acoustic occupancy level**  
Metal ceilings are particularly suitable for combination with water-bearing heat exchangers for room temperature control. Fitting the ceiling with cooling systems changes the acoustic properties of the ceiling panels, because the previously continuous holes of profiles are covered. Therefore the "acoustic occupancy level" is specified in the tables. This means the proportion of the area covered by the heat conducting profile.



	Fural
Perforation Ø	Rd 1.8 - 21 %
Hole content	1.8 mm
Max. perforation width	21 %
Des. acc. to DIN 24041	1,400 mm
Horizontal spacing	Rd 1.80 - 3.50
Vertical spacing	4.96 mm →
Diagonal spacing	2.48 mm ↓
Perforation direction	3.50 mm ↘
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz], <b>Fleece and cooling system plus mineral wool in PE</b>
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M61840/12 + <a href="#">M61840/15</a>
NRC	0.70; <b>0.95</b>
$a_w$	0.65; <b>0.95</b>
Absorber class	C (DIN EN 11654), A (DIN EN 11654)
Acoustic infill	<b>40 mm mineral wool 45 kg/m³ in PE film + Temperon cooling system</b>
Acoustic occ. level	29% [cooling system]

	Fural
Perforation Ø	Rg 2.5 - 16 %
Hole content	2.5 mm
Max. perforation width	16 %
Des. acc. to DIN 24041	1,140 mm
Horizontal spacing	Rg 2.50 - 5.50
Vertical spacing	5.50 mm →
Diagonal spacing	5.50 mm ↓
Perforation direction	7.78 mm ↘
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz], <b>Fleece and cooling system plus mineral wool in PE</b>
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M61840/14 + <a href="#">M61840/11</a>
NRC	0.75; <b>0.95</b>
$a_w$	0.70 (L); <b>0.90 (L)</b>
Absorber class	C (DIN EN 11654), A (DIN EN 11654)
Acoustic infill	<b>40 mm mineral wool 45 kg/m³ in PE film + Temperon cooling system</b>
Acoustic occ. level	29% [cooling system]





# FLOATING CEILINGS

## Special acoustic features of floating ceilings

In contrast to closed ceiling systems, it is not appropriate to specify sound absorption values for individual absorbers. Thanks to the additional absorbent rear side of floating ceilings, excellent acoustic results are achievable on paper (e.g.  $\alpha_w = 1.6$ ), which cannot be accounted for meaningfully. Furthermore, the edge diffraction and the ratio of perimeter to area of a floating ceiling have a certain influence that cannot be determined directly. These effects mean that floating ceilings have **better sound absorption** than closed ceilings.

Therefore the **equivalent sound absorption area** is specified for individual absorbers, rather than the sound absorption coefficient:

The following example shows how much flat ceiling a floating ceiling can replace in order to achieve the same acoustic effect.

**Schuler, Göppingen**  
 - Architect: Holzbauer & Partner  
 - Offices  
 - Perforation Rg 2.5 - 16 %  
 - Colour RAL 9016 traffic white  
 - Multi-floating ceiling system with hang-in tiles



## Example

- Room situation with dimensions  $l=10 \text{ m}$ ,  $w=10 \text{ m}$ ,  $h=3 \text{ m}$
- Floor space:  $100 \text{ m}^2$
- Room volume  $V: 300 \text{ m}^3$
- Carpet ( $100 \text{ m}^2$ ):  $\alpha=0.06$
- Plastered ceiling and wall ( $190 \text{ m}^2$ ):  $\alpha=0.03$
- Glass window front ( $30 \text{ m}^2$ ):  $\alpha=0.01$
- Unfurnished

## Formulae

- Equivalent sound absorption area  $A$  ( $\alpha$  = degree of absorption,  $S$  = area):  

$$A=\alpha \times S$$
- Reverberation time  $T$  ( $V$  = volume):  

$$T=0.163 \times V/A$$
  
 (Sabine formula)

Recommended reverberation time $T \sim 0.6 \text{ s}$ (DIN 18041)		Initial situation of a plastered, reverberant ceiling		All-over metal ceiling Fural Rg 2.5 - 16 % with 30 mm mineral wool 45 kg/m³ in PE film		Floating ceilings Fural Rg 2.5 - 16 % with 50 mm mineral wool 100 kg/m³ in PE film	
T	Calculated reverberation time	3.0 s	0.6 s	0.6 s			
S	Area of metal ceiling	-	75.0 m²	49.0 m²	$\sim 17x$		
A	Equivalent sound absorption area of the whole room	16.0 m²	81.8 m²	82.3 m²			

(The individual calculations can be found on the next page.)

## Conclusion

In order to achieve the same acoustic effect in a room, a much smaller area is required if floating ceilings are used. The additional physical dampening effects can yield a **material saving of up to 30%**.

## The benefits of floating ceilings

- Additionally absorbent rear side
- Saving of ~ 30% material area compared to a metal ceiling
- More flexible in terms of layout
- Existing lighting may continue to be used
- Straightforward retrofitting
- Can be used or retrofitted during building core activation
- Simple subsequent air conditioning

# PRACTICAL EXAMPLE

The sample calculation is based on an exemplary initial situation and compares the areas of metal ceiling (method 1) and floating ceiling (method 2) required to achieve a reverberation time of 0.6 s as per DIN 18041.

- Sandgruben Secondary School, Basel**
- Architecture:  
Stücheli Architekten AG, Zürich
  - Expanded metal floating ceiling
  - Mesh 20.0 x 10.0 x 2.0 x 1.5 mm  
(L x W x B x A)
  - Colour RAL 9006 white aluminium
  - Z hang-in system
  - Tile type B

## Calculations

### Initial situation

Walls, ceilings  $S=190 \text{ m}^2 \alpha=0.03$  (at 500 Hz as per DIN 18041)

Window front  $S=30 \text{ m}^2 \alpha=0.11$  (at 500 Hz as per DIN 18041)

Carpet, short  $S=100 \text{ m}^2 \alpha=0.07$  (at 500 Hz as per DIN 18041)

Walls + raw ceiling  $190 \text{ m}^2 \times 0.03 = 5.7 \text{ m}^2$

Window front  $30 \text{ m}^2 \times 0.11 = 3.3 \text{ m}^2$

Carpet  $100 \text{ m}^2 \times 0.07 = 7.0 \text{ m}^2$

Total  $16.0 \text{ m}^2$

$T=0.163 \times 300/16 = 3.0 \text{ s} >> 0.6 \text{ s}$  (requirement as per DIN 18041)

### Method 1

Install a metal ceiling, all-over  
( $75 \text{ m}^2$  in perforated version,  $25 \text{ m}^2$  plain)

Perforated metal ceiling  $S=75 \text{ m}^2 \alpha=0.90$

(at 500 Hz acc. to test report P-BA 279/2006 Figure 17; see page 34)

Plain metal ceiling  $S=25 \text{ m}^2 \alpha=0.05$

(at 500 Hz acc. to test report P-BA 279/2006 Figure 31; on request)

Walls  $90 \text{ m}^2 \times 0.03 = 2.7 \text{ m}^2$

Window front  $30 \text{ m}^2 \times 0.11 = 3.3 \text{ m}^2$

Carpet  $100 \text{ m}^2 \times 0.07 = 7.0 \text{ m}^2$

Perf. metal ceiling  $75 \text{ m}^2 \times 0.90 = 67.5 \text{ m}^2$

Plain metal ceiling  $25 \text{ m}^2 \times 0.05 = 1.25 \text{ m}^2$

Total  $81.8 \text{ m}^2$

$T=0.163 \times 300/81.8 = 0.6 \text{ s}$

### Method 2

Install 17x floating ceilings @  $2.88 \text{ m}^2$   
(total area  $48.96 \text{ m}^2$ )

A =  $3.9 \text{ m}^2$  each

(at 500 Hz acc. to test report 07/12/2010 M 61840/20; see page 65)

Walls and raw ceiling  $190 \text{ m}^2 \times 0.03 = 5.7 \text{ m}^2$


Carpet  $100 \text{ m}^2 \times 0.07 = 7.0 \text{ m}^2$

Window front  $30 \text{ m}^2 \times 0.11 = 3.3 \text{ m}^2$

Floating ceiling  $3.9 \text{ m}^2$  each  $\times 17 = 66.3 \text{ m}^2$



Total  $82.3 \text{ m}^2$

$T=0.163 \times 300/82.3 = 0.6 \text{ s}$




# FLOATING CEILINGS

Schuler AG, Göppingen




<b>Fural</b>	
Perforation Ø	Rv 1.6 - 20 %
1.6 mm	
Hole content	20 %
Max. perforation width	1,450 mm
Des. acc. to DIN 24041	Rv 1.60 - 3.50
Horizontal spacing	3.50 mm →
Vertical spacing	3.03 mm ↓
Offset spacing 60°	3.50 mm ↓
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/21
Equiv. sound absorp.	[500 Hz] 3.8 m <sup>2</sup>
Visible surface area	2.88 m <sup>2</sup>
<b>Acoustic infill</b>	50 mm mineral wool 100 kg/m <sup>3</sup> in PE film


<b>Fural</b>	
Perforation Ø	Rv 1.6 - 20 %
1.6 mm	
Hole content	20 %
Max. perforation width	1,450 mm
Des. acc. to DIN 24041	Rv 1.60 - 3.50
Horizontal spacing	3.50 mm →
Vertical spacing	3.03 mm ↓
Offset spacing 60°	3.50 mm ↓
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/18
Equiv. sound absorp.	[500 Hz] 3.8 m <sup>2</sup>
Visible surface area	2.88 m <sup>2</sup>
<b>Acoustic infill</b>	50 mm mineral wool 150 kg/m <sup>3</sup> in PE film



**Floating ceilings**  
Floating ceilings can be used both as individual elements and as multi-part, combined units.




<b>Fural</b>	
Perforation Ø	Rg 2.5 - 16 %
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/20
Equiv. sound absorp.	[500 Hz] 3.9 m <sup>2</sup>
Visible surface area	2.88 m <sup>2</sup>
<b>Acoustic infill</b>	50 mm mineral wool 100 kg/m <sup>3</sup> in PE film

<b>Fural</b>	
Perforation Ø	Rg 2.5 - 16 %
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→




Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/17
Equiv. sound absorp.	[500 Hz] 3.9 m <sup>2</sup>
Visible surface area	2.88 m <sup>2</sup>
<b>Acoustic infill</b>	50 mm mineral wool 150 kg/m <sup>3</sup> in PE film




# COOLING FLOATING CEILINGS 1



European Investment Bank, Luxembourg




**Fural**  
Perforation Ø  
Hole content  
Max. perforation width  
Des. acc. to DIN 24041  
Horizontal spacing  
Vertical spacing  
Diagonal spacing  
Perforation direction  
→

**Sound absorption**


Overall structure  
Fleece  
Test certificate  
Equiv. sound absorp.  
Visible surface area

**Acoustic infill**

Acoustic occ. level  
73% [cooling system with 12 heat conducting profiles]





**Fural**  
Perforation Ø  
Hole content  
Max. perforation width  
Des. acc. to DIN 24041  
Horizontal spacing  
Vertical spacing  
Diagonal spacing  
Perforation direction  
→

**Sound absorption**


Overall structure  
Fleece  
Test certificate  
Equiv. sound absorp.  
Visible surface area

**Acoustic infill**

Acoustic occ. level  
73% [cooling system with 12 heat conducting profiles]



**Room temperature control by floating ceiling**

Floating ceilings are particularly suitable for combination with water-bearing heat exchangers for room temperature control. Fitting with cooling systems changes the acoustic properties of the floating ceilings, because the previously continuous holes of profiles are covered. Therefore the "acoustic occupancy level" is specified in the tables. This means the proportion of the area covered by the heat conducting profile.


**Edge formation of floating ceilings**

The edge formation of floating ceilings can be implemented with internal angles of 90°, 60° or 45°. While internal angles of 90° create a voluminous impression, the versions with internal angles of 60° and 45° have a more two-dimensional effect.

# COOLING FLOATING CEILINGS 2




<b>Fural</b>
Rv 1.6 - 20 %
1.6 mm
20 %
Max. perforation width
Des. acc. to DIN 24041
Horizontal spacing
Vertical spacing
Offset spacing 60°
Perforation direction

**Sound absorption**



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/16
Equiv. sound absorp.	[500 Hz] 2.5 m <sup>2</sup>
Visible surface area	2.88 m <sup>2</sup>
<b>Acoustic infill</b>	<b>Temperon cooling system</b>
Acoustic occ. level	30 %



<b>Fural</b>
Rg 2.5-16 %
2.5 mm
16 %
Max. perforation width
Des. acc. to DIN 24041
Horizontal spacing
Vertical spacing
Diagonal spacing
Perforation direction

**Sound absorption**



Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/19
Equiv. sound absorp.	[500 Hz] 2.6 m <sup>2</sup>
Visible surface area	2.88 m <sup>2</sup>
<b>Acoustic infill</b>	<b>Temperon cooling system</b>
Acoustic occ. level	30 %


**Room temperature control by floating ceiling**


Floating ceilings are particularly suitable for combination with water-bearing heat exchangers for room temperature control. Fitting with cooling systems changes the acoustic properties of the floating ceilings, because the previously continuous holes of profiles are covered. Therefore the "acoustic occupancy level" is specified in the tables. This means the proportion of the area covered by the heat conducting profile.

**Edge formation of floating ceilings**


The edge formation of floating ceilings can be implemented with internal angles of 90°, 60° or 45°. While internal angles of 90° create a voluminous impression, the versions with internal angles of 60° and 45° have a more two-dimensional effect.



# ACOUSTIC WALLS 1




	Fural
Perforation Ø	Rg 0.7 - 1%
Hole content	0.7 mm
Max. perforation width	1 %
Des. acc. to DIN 24041	1,140 mm
Horizontal spacing	Rg 0.70 - 6.00
Vertical spacing	6.00 mm →
Diagonal spacing	6.00 mm ↓
Perforation direction	8.48 mm ↘
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz]



Overall structure	50 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/27
NRC	0.55
$a_w$	0.40 (L)
Absorber class	D (DIN EN 11654)

**Acoustic infill** 50 mm mineral wool 100 kg/m<sup>3</sup> in PE film




Overall structure	50 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/26
NRC	0.85
$a_w$	0.80 (L)
Absorber class	B (DIN EN 11654)

**Acoustic infill** 50 mm mineral wool 100 kg/m<sup>3</sup> in PE film




## Clip-in system




Overall structure


## Hang-in system



Overall structure




	Fural
Perforation Ø	Rv 1.6 - 20 %
Hole content	1.6 mm
Max. perforation width	20 %
Des. acc. to DIN 24041	1,450 mm
Horizontal spacing	Rv 1.60 - 3.50
Vertical spacing	3.50 mm →
Offset spacing 60°	3.03 mm ↓
Perforation direction	3.50 mm ↘
Sound absorption	Sound absorption coefficient $a_s$ at one-third centre frequency f [Hz]



Overall structure	50 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/22
NRC	0.95
$a_w$	0.95
Absorber class	A (DIN EN 11654)

**Acoustic infill** 50 mm mineral wool 100 kg/m<sup>3</sup> in PE film




Overall structure	50 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/25
NRC	0.95
$a_w$	0.95
Absorber class	A (DIN EN 11654)

**Acoustic infill** 50 mm mineral wool 100 kg/m<sup>3</sup> in PE film




# ACOUSTIC WALLS 2

Tyrol Control Centre, Innsbruck



	<b>Fural</b>
Perforation Ø	Rg 2.5 - 16 %
Hole content	2.5 mm
Max. perforation width	16 %
Des. acc. to DIN 24041	1.460 mm
Horizontal spacing	Rg 2.50 - 5.50
Vertical spacing	5.50 mm →
Diagonal spacing	5.50 mm ↓
Perforation direction	7.78 mm ↓
→	Offset spacing 60°




Overall structure	50 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/23
NRC	0.90
$\alpha_w$	0.90
Absorber class	A (DIN EN 11654)

**Acoustic infill** 50 mm mineral wool 100 kg/m<sup>3</sup> in PE film





	<b>Fural</b>
Perforation Ø	Rv 3.0 - 20 %
Hole content	3.0 mm
Max. perforation width	20 %
Des. acc. to DIN 24041	1.447 mm
Horizontal spacing	Rv 3.00 - 6.35
Vertical spacing	3.25 mm →
Offset spacing 60°	5.50 mm ↓
Perforation direction	6.35 mm ↓
→	



Overall structure	50 mm
Fleece	Bonded acoustic fleece
Test certificate	07.12.2010 M 61840/24
NRC	0.90
$\alpha_w$	0.90
Absorber class	A (DIN EN 11654)

**Acoustic infill** 50 mm mineral wool 100 kg/m<sup>3</sup> in PE film





## Substructure of acoustic walls

Acoustic walls can be installed using the same grid and clamping profiles that are used for metal ceilings.


# L-ABSORBERS

Rudolf Diesel Municipal Secondary School, Munich



<b>Fural</b>
Rg 0.7 - 4 %
Perforation Ø 0.7 mm
Hole content 4 %
Max. perforation width 1,140 mm
Des. acc. to DIN 24041
Horizontal spacing 3.00 mm →
Vertical spacing 3.00 mm ↓
Diagonal spacing 4.42 mm ↘
Perforation direction →

## Sound absorption




## Overall structure

Length	1,000 mm
Fleece	Bonded acoustic fleece
Test certificate	22.12.2017 M105629/33
NRC	0.70
$\alpha_w$	0.65
Absorber class	C (DIN EN 11654)
Acoustic infill	60 mm sheep's wool 20 kg/m³




<b>Fural</b>
Rg 2.5 - 16 %
Perforation Ø 2.5 mm
Hole content 16 %
Max. perforation width 1,140 mm
Des. acc. to DIN 24041
Horizontal spacing 5.50 mm →
Vertical spacing 5.50 mm ↓
Diagonal spacing 7.78 mm ↘
Perforation direction →

## Sound absorption



## Overall structure

Length	1,000 mm
Fleece	Bonded acoustic fleece
Test certificate	22.12.2017 M105629/33
NRC	0.70
$\alpha_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	60 mm sheep's wool 20 kg/m³



## Product description

The L-shaped absorber element consists of metal components arranged at right angles to each other in the room border between wall and ceiling. The absorber elements are only attached to the wall, in order not to load the ceiling statically. The one-piece design results in a precise joint pattern and quick installation. The distance between metal elements and ceiling is variable. The metal elements are coated with acoustic fleece on the back. 60 mm-thick acoustic inlays are employed as cavity soundproofing.

## Acoustic

L-absorbers impress with their high acoustic effectiveness and high-quality appearance. One of the most important criteria for the quality of a room is optimum room acoustics.



#### Longitudinal sound insulation in dry-wall construction

Particularly with dry walls, the longitudinal sound insulation of the ceiling is a major factor in the acoustic function of a room. The sound penetrates through the ceiling into the ceiling void and is transmitted to the adjoining room. There the sound waves pass through the ceiling again and can be heard in the room as residual noise. The difference between the transmitted noise level and the received noise level is referred to as normalised flanking level difference and can be tested in the laboratory.

#### Outstanding insulation values

In the tests conducted according to DIN EN ISO 10848-2, Fural achieved outstanding results. Strip-grid and clip-in strip grid systems with the following structure were tested:

- Perforated Fural metal ceiling
- Mineral wool inlay sealed in PE film
- Plasterboard or steel cover

The systems enable quick and flexible adaptation of the rooms for the developer or tenant in the event of changes in use. Thanks to the excellent insulation values, components such as plasterboard partitions can be omitted, which results in significant potential savings.

Even in the case of ceiling panels that have been fitted additionally with cooling and heating coils, this has no further effect on the longitudinal sound insulation factor. The specified values are also achieved in this setup.


#### Values achieved

Ceiling tile with plasterboard cover: up to 56 dB; ceiling tile with steel cover: up to 52 dB.

#### Measurement and evaluation


The normalised flanking level difference is tested as per DIN EN ISO 10848-2. In this test, a suspended ceiling that extends over two adjoining rooms is installed above a standard partition wall in the test laboratory. A transmitter (loudspeaker) is installed in one room and a receiver (microphone) in the other. The transmitted, defined noise is measured as incoming noise in the receiving room. The resulting measurement curve is evaluated as per ISO 717-1 in a frequency range from 100 Hz to 5000 Hz.

The higher the weighted normalised flanking sound level difference,  $D_{n,f,w}$ , the better the sound insulating properties that the component possesses. The C and  $C_{tr}$  values provide additional information about a component's properties. C provides information about the insulating properties against balanced frequency spectra, such as office, residential and traffic noises. The  $C_{tr}$  value can be used for assessing noises with a large low-frequency content (aircraft noise, traffic noise).




# CLIP-IN STRIP-GRID CEILINGS

Bügelbauten, Berlin Central Station



<b>Fural</b>	
Perforation Ø	Rg 2.5-16%
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→

## Sound absorption




Overall structure  
Fleece  
Test certificate  
Weighted normalised  
flanking sound level  
difference  $D_{n,tw}$  [C;C<sub>tr</sub>]  
27 [-1; -3] dB

Acoustic infill  
30 mm mineral wool 45 kg/m<sup>3</sup> in PE film


<b>Fural</b>	
Perforation Ø	Rg 2.5-16%
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→

## Sound absorption



Overall structure  
Fleece  
Test certificate  
Weighted normalised  
flanking sound level  
difference  $D_{n,tw}$  [C;C<sub>tr</sub>]  
44 [-1; -6] dB


Acoustic infill  
30 mm mineral wool 45 kg/m<sup>3</sup> in PE film +  
12.5 mm plasterboard



## Clip-in strip-grid systems


Clip-in strip-grid ceilings impress with their outstanding appearance. The high-precision double clip-in studs allow the tiles to be fitted without stress and without any height differences viewed from below.

The advantage of the clip-in strip-grid system is that the strip grids can be removed from the ceiling assembly at any time, without adjoining fields having to be removed. This is possible because the support frame takes on the essential load-bearing function.



<b>Fural</b>	
Perforation Ø	Rg 2.5 - 16 %
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	5.50 mm ↓
Perforation direction	7.78 mm ↓
→	

**Sound absorption** Normalised flanking sound level difference at frequency



Overall structure  
Fleece  
Test certificate  
Weighted normalised  
flanking sound level  
difference  $D_{n,tw} [C; C_{tr}]$   
**Acoustic infill**

w/o

14 [0; 0] dB


720 mm  
Bonded acoustic fleece  
07.12.2010 M 61840/28

Overall structure  
Fleece  
Test certificate  
Weighted normalised  
flanking sound level  
difference  $D_{n,tw} [C; C_{tr}]$   
**Acoustic infill**

26 [-1; -3] dB


30 mm mineral wool 45 kg/m³ in PE film

720 mm  
Bonded acoustic fleece  
07.12.2010 M 61840/29




#### Strip-grid systems

Strip grids offer designers greater flexibility: The ceiling pattern can be adapted on the construction grid, dividing walls can be incorporated in the system and the ceiling can meet stringent longitudinal sound insulation requirements.



<b>Fural</b>	
Perforation Ø	Rg 2.5 - 16 %
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	5.50 mm ↓
Perforation direction	7.78 mm ↓
→	

**Sound absorption** Normalised flanking sound level difference at frequency



Overall structure  
Fleece  
Test certificate  
Weighted normalised  
flanking sound level  
difference  $D_{n,tw} [C; C_{tr}]$   
**Acoustic infill**

52 [-2; -9] dB


30 mm mineral wool 45 kg/m³ in PE film +  
1.0 mm sheet steel cover

720 mm  
Bonded acoustic fleece  
07.12.2010 M 61840/30



<b>Fural</b>	
Perforation Ø	Rg 2.5 - 16 %
2.5 mm	
Hole content	16 %
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	5.50 mm ↓
Perforation direction	7.78 mm ↓
→	

**Sound absorption** Normalised flanking sound level difference at frequency




Overall structure  
Fleece  
Test certificate  
Weighted normalised  
flanking sound level  
difference  $D_{n,tw} [C; C_{tr}]$   
**Acoustic infill**

56 [-4; -11] dB

30 mm mineral wool 45 kg/m³ in PE film +  
12.5 mm plasterboard




# TESTED PERFORATIONS 1





<b>Fural</b>	
Rg 0.7-1%	
Perforation Ø	0.7 mm
Hole content	1 %
Max. perforation width	1,197 mm
Des. acc. to DIN 24041	Rg 0.70 - 6.00
Horizontal spacing	6.00 mm →
Vertical spacing	6.00 mm ↓
Diagonal spacing	8.48 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	31/08/2007 P-BA 231/2007
NRC	0.65
$a_w$	0.50 (LM)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o

<b>Fural</b>	
Rg 0.7-1.5%	
Perforation Ø	0.7 mm
Hole content	1.5 %
Max. perforation width	1,400 mm
Des. acc. to DIN 24041	Rg 0.70 - 5.00
Horizontal spacing	5.00 mm →
Vertical spacing	5.00 mm ↓
Diagonal spacing	7.07 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	04/12/2019 M105629
NRC	0.60
$a_w$	0.50 (L)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o





<b>Fural</b>	
Rg 0.8-6%	
Perforation Ø	0.8 mm
Hole content	6 %
Max. perforation width	1,400 mm
Des. acc. to DIN 24041	Rg 0.80 - 3.00
Horizontal spacing	3.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	09/06/2017 M105629/17
NRC	0.75
$a_w$	0.75
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o



<b>Fural</b>	
Rg 0.7-4 %	
Perforation Ø	0.7 mm
Hole content	4 %
Max. perforation width	1,197 mm
Des. acc. to DIN 24041	Rg 0.70 - 3.00
Horizontal spacing	3.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	31/08/2007 P-BA 219/2007
NRC	0.80
$a_w$	0.75 (LM)
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o





<b>Fural</b>	
Rg 0.9-7%	
Perforation Ø	0.9 mm
Hole content	7 %
Max. perforation width	1,022 mm
Des. acc. to DIN 24041	Rg 0.90 - 3.00
Horizontal spacing	3.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	30/09/2019 M105629/44
NRC	0.75
$a_w$	0.70
Absorber class	C (DIN EN 11654)
Acoustic infill	w/o



<b>Fural</b>	
Rg 0.9-14 %	
Perforation Ø	0.9 mm
Hole content	14 %
Max. perforation width	1,022 mm
Des. acc. to DIN 24041	Rd 0.90 - 2.12
Horizontal spacing	3.00 mm →
Vertical spacing	1.50 mm ↓
Diagonal spacing	2.12 mm ↘
Perforation direction	→
Overall structure	400 mm
Fleece	Bonded acoustic fleece
Test certificate	17/11/2012 7178-12-2
NRC	0.55
$a_w$	0.55 (LM)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o

<b>Fural</b>	
Rg 0.7-1.5%	
Perforation Ø	0.7 mm
Hole content	1.5 %
Max. perforation width	1,400 mm
Des. acc. to DIN 24041	Rg 0.70 - 5.00
Horizontal spacing	5.00 mm →
Vertical spacing	5.00 mm ↓
Diagonal spacing	7.07 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	04/12/2019 M105629
NRC	0.60
$a_w$	0.50 (L)
Absorber class	D (DIN EN 11654)
Acoustic infill	w/o

# TESTED PERFORATIONS 2






<b>Fural</b>	
Rg 1.5 - 11%	
Perforation Ø	1.5 mm
Hole content	11%
Max. perforation width	1,488 mm
Des. acc. to DIN 24041	Rg 1.50 - 4.00
Horizontal spacing	4.00 mm →
Vertical spacing	4.00 mm ↓
Diagonal spacing	5.65 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07/12/2010 M 61840/6
NRC	0.80
$a_w$	0.75
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o

<b>Fural</b>	
Rd 1.5 - 11%	
Perforation Ø	1.5 mm
Hole content	11%
Max. perforation width	1,470 mm
Des. acc. to DIN 24041	Rd 1.50 - 4.00
Horizontal spacing	5.66 mm →
Vertical spacing	2.83 mm ↓
Diagonal spacing	4.00 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07/12/2010 M 61840/6
NRC	0.80
$a_w$	0.75
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o

<b>Fural</b>	
Rv 1.6 - 20 %	
Perforation Ø	1.6 mm
Hole content	20%
Max. perforation width	1,450 mm
Des. acc. to DIN 24041	Rv 1.60 - 3.50
Horizontal spacing	3.50 mm →
Vertical spacing	3.03 mm ↓
Offset spacing 60°	3.50 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	14/12/2006 P-BA 279/2006
NRC	0.74
$a_w$	0.80
Absorber class	B [DIN EN 11654]
Acoustic infill	w/o

<b>Fural</b>	
Rd 1.6 - 22 %	
Perforation Ø	1.6 mm
Hole content	22%
Max. perforation width	636.4 mm
Des. acc. to DIN 24041	Rd 1.60 - 3.00
Horizontal spacing	4.30 mm →
Vertical spacing	2.15 mm ↓
Diagonal spacing	3.00 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	09/06/2017 M 105629/19
NRC	0.70
$a_w$	0.70
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o




<b>Fural</b>	
Rd 1.5 - 22 %	
Perforation Ø	1.5 mm
Hole content	22%
Max. perforation width	1,488 mm
Des. acc. to DIN 24041	Rd 1.50 - 2.83
Horizontal spacing	4.00 mm →
Vertical spacing	2.00 mm ↓
Diagonal spacing	2.83 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07/12/2010 M 61840/5
NRC	0.70
$a_w$	0.70
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o


<b>Fural</b>	
Rg 1.8 - 10 %	
Perforation Ø	1.8 mm
Hole content	10%
Max. perforation width	1,400 mm
Des. acc. to DIN 24041	Rg 1.80 - 4.95
Horizontal spacing	4.95 mm →
Vertical spacing	4.95 mm ↓
Diagonal spacing	7.00 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07/12/2010 M 61840/4
NRC	0.80
$a_w$	0.75
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o

<b>Fural</b>	
Rd 1.8 - 10 %	
Perforation Ø	1.8 mm
Hole content	10%
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rd 1.80 - 4.95
Horizontal spacing	7.00 mm →
Vertical spacing	3.50 mm ↓
Diagonal spacing	4.95 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07/12/2010 M 61840/4
NRC	0.80
$a_w$	0.75
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o


# TESTED PERFORATIONS 3




<b>Fural</b>	
Rg 1.8 - 20 %	
Perforation Ø	1.8 mm
Hole content	20%
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 1.80 - 3.50
Horizontal spacing	3.50 mm →
Vertical spacing	3.50 mm ↓
Diagonal spacing	4.95 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 220/2007 Figure 2
NRC	0.75
$a_w$	0.75
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o




<b>Fural</b>	
Rd 1.8 - 21 %	
Perforation Ø	1.8 mm
Hole content	21%
Max. perforation width	1,400 mm
Des. acc. to DIN 24041	Rd 1.80 - 3.50
Horizontal spacing	4.96 mm →
Vertical spacing	2.48 mm ↓
Diagonal spacing	3.50 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	31/08/2007 P-BA 220/2007 Figure 2
NRC	0.75
$a_w$	0.75
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o




<b>Fural</b>	
Rv 2.5 - 23 %	
Perforation Ø	2.5 mm
Hole content	23%
Max. perforation width	1,467 mm
Des. acc. to DIN 24041	Rv 2.50 - 5.00
Horizontal spacing	8.66 mm →
Vertical spacing	2.50 mm ↓
Offset spacing 60°	5.00 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	07/12/2010 M 61840/7
NRC	0.75
$a_w$	0.75 (L)
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o




<b>Fural</b>	
Rd 2.8 - 20 %	
Perforation Ø	2.8 mm
Hole content	20%
Max. perforation width	627.9 mm
Des. acc. to DIN 24041	Rd 2.80 - 5.50
Horizontal spacing	7.80 mm →
Vertical spacing	3.90 mm ↓
Diagonal spacing	5.50 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	09/06/2017 M 105629/20
NRC	0.75
$a_w$	0.75
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o




<b>Fural</b>	
Rd 2.5 - 8 %	
Perforation Ø	2.5 mm
Hole content	8%
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rd 2.50 - 7.80
Horizontal spacing	11.0 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	14/12/2006 P-BA 279/2006 Figure 5
NRC	0.80
$a_w$	0.75
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o



<b>Fural</b>	
Rg 2.5 - 16 %	
Perforation Ø	2.5 mm
Hole content	16%
Max. perforation width	1,460 mm
Des. acc. to DIN 24041	Rg 2.50 - 5.50
Horizontal spacing	5.50 mm →
Vertical spacing	5.50 mm ↓
Diagonal spacing	7.78 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	14/12/2006 P-BA 279/2006 Figure 1
NRC	0.80
$a_w$	0.80
Absorber class	B [DIN EN 11654]
Acoustic infill	w/o




<b>Fural</b>	
Rg 3.0 - 20 %	
Perforation Ø	3.0 mm
Hole content	20%
Max. perforation width	1,434 mm
Des. acc. to DIN 24041	Rg 3.00 - 6.00
Horizontal spacing	6.0 mm →
Vertical spacing	6.0 mm ↓
Diagonal spacing	8.48 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 221/2007 Figure 2
NRC	0.80
$a_w$	0.75 (L)
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o




<b>Fural</b>	
Rv 3.0 - 20 %	
Perforation Ø	3.0 mm
Hole content	20%
Max. perforation width	1,402 mm
Des. acc. to DIN 24041	Rv 3.00 - 6.35
Horizontal spacing	6.50 mm →
Vertical spacing	5.50 mm ↓
Offset spacing 60°	6.39 mm ↘
Perforation direction	→
Overall structure	200 mm
Fleece	Bonded acoustic fleece
Test certificate	P-BA 221/2007 Figure 2
NRC	0.80
$a_w$	0.75 (L)
Absorber class	C [DIN EN 11654]
Acoustic infill	w/o


# TESTED PERFORATIONS 4




<b>Fural</b>
Rg 4.0 - 17 %
Perforation Ø 4.0 mm
Hole content 17 %
Max. perforation width 1,453 mm
Des. acc. to DIN 24041
Horizontal spacing 8.60 mm →
Vertical spacing 8.60 mm ↓
Diagonal spacing 12.1 mm ↘
Perforation direction →
Overall structure Fleece
Test certificate P-BA 279/2006 Figure 7
NRC 0.80
$a_w$ 0.80
Absorber class B [DIN EN 11654]
Acoustic infill w/o





<b>Fural</b>
Rd 4.0 - 33 %
Perforation Ø 4.0 mm
Hole content 33 %
Max. perforation width 1,450 mm
Des. acc. to DIN 24041
Horizontal spacing 8.60 mm →
Vertical spacing 4.30 mm ↓
Diagonal spacing 6.10 mm ↘
Perforation direction →
Overall structure Fleece
Test certificate P-BA 279/2006 Figure 3
NRC 0.80
$a_w$ 0.80
Absorber class B [DIN EN 11654]
Acoustic infill w/o




<b>Fural</b>
Qg 4.0 - 33 %
Perforation Ø 4.0 mm
Hole content 33 %
Max. perforation width 630 mm
Des. acc. to DIN 24041
Horizontal spacing 7.00 mm →
Vertical spacing 7.00 mm ↓
Diagonal spacing 9.89 mm ↘
Perforation direction →
Overall structure Fleece
Test certificate P-BA 279/2006 Figure 4
NRC 0.80
$a_w$ 0.80
Absorber class B [DIN EN 11654]
Acoustic infill w/o




<b>Fural</b>
Rv 4.5 - 51 %
Perforation Ø 4.5 mm
Hole content 51 %
Max. perforation width 627 mm
Des. acc. to DIN 24041
Horizontal spacing 10.4 mm →
Vertical spacing 3.00 mm ↓
Offset spacing 60° 6.00 mm ↘
Perforation direction →
Overall structure Fleece
Test certificate 09/06/2017 M105629/21
NRC 0.65
$a_w$ 0.65 (L)
Absorber class C [DIN EN 11654]
Acoustic infill w/o



<b>Fural</b>
Rg 14.0 - 23 %
Perforation Ø 14.0 mm
Hole content 23 %
Max. perforation width 598 mm
Des. acc. to DIN 24041
Horizontal spacing 26.00 mm →
Vertical spacing 26.00 mm ↓
Diagonal spacing 36.76 mm ↘
Perforation direction →
Overall structure Fleece
Test certificate P-BA 279/2006 Figure 8
NRC 0.75
$a_w$ 0.75 (L)
Absorber class C [DIN EN 11654]
Acoustic infill w/o




# UNTESTED PERFORATIONS




<b>Fural</b>	
Perforation Ø	Rd 0.7 - 2%
0.7 mm	
Hole content	2%
Max. perforation width	1,140 mm
Des. acc. to DIN 24041	Rd 0.70 - 6.00
Horizontal spacing	6.00 mm →
Vertical spacing	3.00 mm ↓
Diagonal spacing	4.24 mm ↘
Perforation direction	→

<b>Fural</b>	
Perforation Ø	Rd 1.5 - 6%
1.5 mm	
Hole content	6%
Max. perforation width	1,486 mm
Des. acc. to DIN 24041	Rd 1.50 - 8.00
Horizontal spacing	8.00 mm →
Vertical spacing	4.00 mm ↓
Diagonal spacing	5.65 mm ↘
Perforation direction	→




<b>Fural</b>	
Perforation Ø	Rg 2.5 - 4%
2.5 mm	
Hole content	4%
Max. perforation width	1,430 mm
Des. acc. to DIN 24041	Rg 2.50 - 12.00
Horizontal spacing	12.00 mm →
Vertical spacing	12.00 mm ↓
Diagonal spacing	16.97 mm ↘
Perforation direction	→

<b>Fural</b>	
Perforation Ø	Rg 4.0 - 4%
4.0 mm	
Hole content	4%
Max. perforation width	606 mm
Des. acc. to DIN 24041	Rg 4.00 - 17.20
Horizontal spacing	17.20 mm →
Vertical spacing	17.20 mm ↓
Diagonal spacing	24.32 mm ↘
Perforation direction	→




<b>Fural</b>	
Perforation Ø	Rg 1.8 - 2%
1.8 mm	
Hole content	2%
Max. perforation width	1,413 mm
Des. acc. to DIN 24041	Rg 1.80 - 9.90
Horizontal spacing	9.90 mm →
Vertical spacing	9.90 mm ↓
Diagonal spacing	14.00 mm ↘
Perforation direction	→

<b>Fural</b>	
Perforation Ø	Rd 1.8 - 5%
1.8 mm	
Hole content	5%
Max. perforation width	1,413 mm
Des. acc. to DIN 24041	Rd 1.80 - 7.00
Horizontal spacing	9.90 mm →
Vertical spacing	4.95 mm ↓
Diagonal spacing	7.00 mm ↘
Perforation direction	→



<b>Fural</b>	
Perforation edge	Qg 4.0 - 8%
4.0 mm	
Hole content	8%
Max. perforation width	630 mm
Des. acc. to DIN 24041	Qg 4.00 - 14.00
Horizontal spacing	14.00 mm →
Vertical spacing	14.00 mm ↓
Diagonal spacing	19.79 mm ↘
Perforation direction	→

<b>Fural</b>	
Perforation edge	Qd 4.0 - 17%
4.0 mm	
Hole content	17%
Max. perforation width	630 mm
Des. acc. to DIN 24041	Qd 4.00 - 7.00
Horizontal spacing	14.00 mm →
Vertical spacing	7.00 mm ↓
Diagonal spacing	9.89 mm ↘
Perforation direction	→





Mitglied der  
**DGNB**  
Deutsche Gesellschaft für Nachhaltiges Bauen  
German Sustainable Building Council



**Climate neutral**  
Print product  
ClimatePartner.com/11293-2007-1001

**Fural**

Systeme in Metall GmbH  
Cumberlandstraße 62  
4810 Gmunden  
Austria  
T +43 7612 74 851 0  
F +43 7612 74 851 11  
E fural@fural.at  
W [fural.com](http://fural.com)

**Metalit**

AG  
Murmattenstrasse 7  
6233 Büron  
Switzerland  
T +41 41 925 60 22  
F +41 41 925 60 29  
E [metalit@metalit.ch](mailto:metalit@metalit.ch)  
W [metalit.ch](http://metalit.ch)

**Dipling**

Werk GmbH  
Königsberger Straße 21  
35410 Frankfurt Hungen  
Germany  
T +49 6402 52 58 77  
F +49 6402 75 85 79  
E [dipling@dipling.de](mailto:dipling@dipling.de)  
W [dipling.de](http://dipling.de)



Sales locations



Production locations

AT Gmunden  
CH Büron  
DE Frankfurt Hungen  
CZ Prachatice



Technical locations

AT Gmunden  
CH Büron  
DE Frankfurt Hungen  
BE Wommelgem  
PL Mikotów